

GOLDEN VALLEY RANCH REGIONAL ROADWAY IMPROVEMENTS

BUDGET COST ESTIMATE

ROADWAY NO. S8: EAST LOOP ROAD FROM POD 3 ENTRY ROAD TO TC CONNECTOR ROAD

NEW COST CODE	DESCRIPTION	UNIT	UNIT COST	QUANTITY	TOTAL
2-12-0200	AGGREGATE BASE	CY	\$ 48.00	9,642.00	\$ 462,816.00
2-12-0200	ASPHALT CONCRETE PAVEMENT, 5-INCH	SY	\$ 13.00	31,556.00	\$ 410,228.00
2-13-0200	CONCRETE CURB, TYPE A	LF	\$ 5.75	11,360.00	\$ 65,320.00
2-13-0200	CONCRETE CURB AND GUTTER, TYPE A	LF	\$ 8.25	11,360.00	\$ 93,720.00
2-13-0200	CONCRETE VALLEY GUTTER, 6-INCH, 3 FEET	SF	\$ 6.00	600.00	\$ 3,600.00
2-13-0400	CONCRETE SIDEWALK, 4-INCH, 5 FEET	SF	\$ 3.50	56,800.00	\$ 198,800.00
2-09-0400	6-INCH PVC WATER MAIN	LF	\$ 20.00	360.00	\$ 7,200.00
2-09-0400	8-INCH PVC WATER MAIN	LF	\$ 40.00	90.00	\$ 3,600.00
2-09-0400	12-INCH PVC WATER MAIN	LF	\$ 60.00	60.00	\$ 3,600.00
2-09-0400	24-INCH PVC WATER MAIN	LF	\$ 140.00	5,680.00	\$ 795,200.00
2-09-0400	FIRE HYDRANT ASSEMBLY	EA	\$ 2,000.00	12.00	\$ 24,000.00
2-14-0600	WATER SERVICE WITH METER	EA	\$ 250.00	3.00	\$ 750.00
2-14-0600	4-INCH PVC IRRIGATION SLEEVE	LF	\$ 7.50	360.00	\$ 2,700.00
2-14-0600	6-INCH PVC IRRIGATION SLEEVE	LF	\$ 13.00	180.00	\$ 2,340.00
2-09-0200	8-INCH SEWER PIPE	LF	\$ 15.00	120.00	\$ 1,800.00
2-09-0200	12-INCH SEWER PIPE	LF	\$ 20.00	5,710.00	\$ 114,200.00
2-09-0200	SEWER MANHOLE, 48 INCH	EA	\$ 5,000.00	12.00	\$ 60,000.00
2-10-0100	GAS LINE, STEEL, 6 INCH	LF	\$ 100.00	5,680.00	\$ 568,000.00
2-10-0500	CONDUIT, PVC, 6 IN. (ELECTRIC)	LF	\$ 7.50	17,040.00	\$ 127,800.00
2-10-0500	MANHOLE, ELECTRIC	EA	\$ 5,000.00	12.00	\$ 60,000.00
2-10-0400	CONDUIT, PVC, 4 IN. (TELEPHONE)	LF	\$ 7.50	22,720.00	\$ 170,400.00
2-10-0400	MANHOLE, TELEPHONE	EA	\$ 5,000.00	12.00	\$ 60,000.00
2-10-0600	CONDUIT, PVC, 3 IN. (CABLE)	LF	\$ 6.00	5,728.00	\$ 34,368.00
2-10-0600	PULL BOX, CABLE	EA	\$ 900.00	6.00	\$ 5,400.00
2-15-0400	TRAFFIC SIGNS WITH METAL SUPPORTS	EA	\$ 100.00	18.00	\$ 1,800.00
2-10-0200	NO. 3-1/2 PULL BOX	EA	\$ 500.00	6.00	\$ 3,000.00
2-10-0200	UNDERGROUND ELECTRICAL SERVICE	EA	\$ 1,500.00	2.00	\$ 3,000.00
2-10-0200	WIRE, 2/C NO. 4 & 1/C NO. 8 COPPER IN 1-1/4-INCH PVC CONDUIT	LF	\$ 3.00	11,600.00	\$ 34,800.00
2-10-0200	STREET LIGHT ASSEMBLY	EA	\$ 3,000.00	68.00	\$ 204,000.00
2-15-0400	PAVEMENT STRIPING	LF	\$ 1.00	24,000.00	\$ 24,000.00
2-15-0400	PAVEMENT MESSAGE MARKINGS	EA	\$ 100.00	36.00	\$ 3,600.00
SUBTOTAL					\$ 3,550,042.00
ENGINEERING & SURVEY @				15.00%	\$ 532,506.30
TOTAL					\$ 4,082,548.30

[illegible]